



580 Wright Avenue, Unit 100
Dartmouth, Nova Scotia, B3B 0H8
Ph: 902-405-4774 Fax: 902-405-3744
www.irriplus.com

Scope of work related to attached quote

Float Assembly

HDPE double ring float c/w 8 in aluminum I-beam and stainless cables and shackles designed to support 7500 lbs

HDPE Pipe and Fusion

Includes 100 feet of 8 in schedule 11 HDPE pipe, elbows, flanges and rings, gaskets, bolts and nuts, fusion labor and fusion equipment.

Electrical Work

Disconnect old pump and reconnect new pump. Disconnect and remove any outdated and unused electrical on walls. Supply and install new disconnect and fuses for pump.

Crane Rental

Remove roof and re-install same on pump house, remove old skid from pump house and install float assembly with pump into the lake. Total allotted time 1 day

Welding Work

Construct and install support brackets for HDPE pipe along rock face as required.

Load Reactors

Used on the output side of the VFD's to keep electrical power consistent to the motors when wire lengths exceed 60 ft total distance between panel and pump. Load reactors already included for supply power to the VFD's